

The cycle time for a delayed coker unit is reduced by externally heating the coke drum (10, 12) near the junction of the drum shell and the supporting skirt thereof prior to beginning the hot coker feed fill step. This reduces the thermal stresses at the area around the welds of the drum skirt.

