

A method for construction of multi-tiered turbine tower includes sequence of its assemblage from up downwards with building-up the tower from below and with step-by step lift of mounted part. With lift of mounted part of wind-power tower windmills of assembled part of tower are put to operation for production of electric energy.