

Method of lining of mine workings penetrated in rocks tending to swelling includes installation of main support of technology given profile, roof lagging and anchoring of swelling rocks of soil of the working, with orientation of axis of the anchors in direction of predicted displacement of swelling rocks. The anchors are installed at section of surface of soil of the working restricted with parallel vertical planes that intersect surface of soil from the longitudinal axis of the working at distance equal to 0.23-0.35 of width of the working.