

The process of explosive destruction rock massifs with complicated structures includes drilling series of wells with sequential loading of explosives, installation of air or inert gaps, filling the well mouth and mounting blast network provided with instant downhole blasting. Charging is carried out by placing explosive charges in situ of rock bedding above and below the cavity, with following installation of detonators in each charge, and in the inclusion places cavities or layers of solid rock air or inert gaps are provided.